

CHILLED WATER EQUIPMENT SCHEDULE

Project: Harborview Lab Expansion | Doc No. M-420 | Rev. A

Tag	Type	Qty	Capacity	Manufacturer
CH-01	Centrifugal Chiller	2	400 tons	York
CH-02	Air-Cooled Chiller	1	150 tons	Carrier
CT-01	Cooling Tower	2	1,200 GPM	Baltimore Aircoil
P-401	CHW Pump	4	800 GPM	Bell & Gossett