

NARRATIVE EQUIPMENT SUMMARY

Project: Harborview Lab Expansion | Doc No. M-900

Hot Water Boiler B-01 is scheduled at quantity 2 with a capacity of 2,000 MBH (Aerco). Centrifugal Chiller CH-01 is scheduled at quantity 2 with a capacity of 400 tons (York). Emergency Generator G-01 is scheduled at quantity 1 with a capacity of 450 kW (Caterpillar).

Confirmation table

Tag	Type	Qty	Capacity	Manufacturer
B-01	Hot Water Boiler	2	2,000 MBH	Aerco
CH-01	Centrifugal Chiller	2	400 tons	York
G-01	Emergency Generator	1	450 kW	Caterpillar